



**NOTE:**

- One complete set of levelling blocks, Base plates and Foundation bolts are included in basic machine as Standard accessories.
- This drawing shows the dimensions of using our standard Foundation kit.
- Foundation holes should be concreted with non-shrink mortar after placing the machine on the foundation.
- When the Table bed is placed on the foundation, the positions of foundation bolts, should be adjusted to be in center of foundation holes.
- Ground durability should be stronger than 8ton/m<sup>2</sup>, therefore please decide concrete thickness and piling depending on the Ground conditions.
- Do not select following places to install the machine.
  - 1) Getting Vibration from another machine or equipment.
  - 2) The place has big fluctuation of temperature.
  - 3) The circumstance to raise the dust.
- Floor cover for pit and safety fence is provided by customer.
- Please confirm the installation space of this machine at the general view.

**注記**

- 本機の据付位置は温度変化の激しい場所、並びに塵埃等の多い場所は避けて下さい。
- 本機の基礎には、8 ton/m<sup>2</sup>以上の地耐力が必要です。地質に応じて、パイルングして下さい。
- 基礎の周囲には、必要に応じて防振帯を設けて下さい。
- 基礎ボルト穴は、機械設置後、無収縮モルタルにより固めて下さい。無収縮モルタルには「エムベコBR0グラウト」等を使用して下さい。
- 基礎コンクリート上面の水平誤差(平面度)は5mm以内として下さい。
- 基礎コンクリート内部には、十分な強度を持たせるよう配筋して下さい。
- ピット部の踏板及び安全柵は貴社にて御準備願います。
- 機台の設置スペースは機組立図で確認願います。

MESSRS 納入先	OMC & 7OMS	PRODUCTION ORDERING NO. MT-1528	8BT
TITLE 説明図 (1/2) Foundation Drawing	NAME OF MACHINE OMC & 7OMS	NAME OF PART 1-16	
1	DRAWN	T. Takai	
2	CHECKED		
3	ASST. MANAGER		
REVISIONS	MANAGER	T. Yanagisawa	
CARRIER	APPROVED	T. Ueda	
1NA11287 OMC & 7OMS, MT-1528	SCALE 1:15	PRODUCTION DWG. NO. 1NA13471	
O-M Ltd.	DATE 07. 7. 12		